

**TAMPA-HILLSBOROUGH COUNTY
EXPRESSWAY AUTHORITY**

Letter of Clarification No. 2

FOR

Invitation to Bid (ITB)

LOAD CENTER UPGRADES

ITB No. O-00918

Letter of Clarification No. 2 ~ ITB No. O-00918

Date of Letter of Clarification: August 13, 2018

To all prospective respondents:

The following responds to questions received on the solicitation reference above:

Question 1:	The HNTB Engineer said that we were going to put a box at the bottom of the new meter, on a new service pole, beside the New load center. And that TECO would be bringing the underground feed to the new service?
Response 1:	The transformers are owned and maintained by the Tampa Hillsborough Expressway Authority. The Contractor is required to set a pull box at the base of the pole where the meter is located. Currently, there is conduit running from the base of the pole where the meter is located, back to the transformer that is located next to the Load Center. The Contractor is to utilize the existing conduit for his power run back to the Load Center. There will be the need to alter the run near the transformer/load center, as the feed now goes directly to the load center instead of the transformer. The pull box at the base of the pole where the meter is located, should have at least six (6) feet of slack power feed inside the box, to accommodate TECO in their final hook up.

Respondents MUST acknowledge receipt of this Letter of Clarification by signing, dating and returning the completed Acknowledgement of Receipt of Letter of Clarification/Addendum form with Respondent's proposal.

All other items, conditions, and specifications in the ITB document not specifically changed by the Addendum remain unchanged.

Please send all questions to THEA's Procurement Manager, Man Le, via email at Man.Le@tampa-xway.com.