

Required RFP Amendments 1/30/23

AMENDMENT

Add the reference documents below and REFERENCE DOCUMENTS; 6th Page at front of document:

Correction: Revised Typical Sections & EB Euclid On-Ramp Alignment on Roll Plot #1 in Preliminary Roadway Concept Plans and Revised Signing Concept Development Plans

LIST OF REFERENCE DOCUMENTS:

R_01 - Original Expressway Plans

R_01.01 – Contract 1 – Gandy to Himes

R_01.02 – Contract 2 – Euclid to MacDill

R_01.03 – Contract 3 – San Pedro South View

R_01.04 – Contract 4 – South View Willow

R_01.05 – Contract 5 – Willow to Bay to Bay

R_01.06 – Contract 6 – Bayshore to Florida

R_01.07 – Contract 8A & 8B

R_01.08 – Contract 9A & 9B

R_02_O-00518 SouthSelmonSafety AsBuiltPlans S_S.zip

R_03 – SS Bridge Load Ratings (Exempt).zip

R_04 - Existing Bridge Plans (Exempt).zip

R_05 – Bridge Inspection Reports (Exempt).zip

R_06 – Pile Driving Data_100332-100333.zip

R_07.01 – Preliminary Roadway Concept Plans_070122 **REV**

R_07.02 – Preliminary Structures Concept Plans

R_07.03 - Signalization Concept Development Plans

R_07.04 - Signing Concept Development Plans **REV**

AMENDMENT

Add the reference documents below and REFERENCE DOCUMENTS; 7th Page at front of document:

Correction: Added HDR ICPR4 files (2), Hillsborough River Bridge Aesthetic Lighting Documents, PCS kmz files of THEA fiber, Tampa Convention Center information, ITS Switch Files, COT Traffic Standards, UAO RGB Plans, SWE As-builts & COT Krause Generator files

R_13 – PD&E Documents

- R_13.01 – Selmon_AirQualityTechnicalMemo_May2021.pdf
- R_13.02 – Selmon_ContaminationScreeningEvaluationReport_May2021.pdf
- R_13.03 – Selmon_CulturalResourceAssessment_June2021.pdf
- R_13.04 – Selmon_NaturalResourcesEvaluation_May2021.pdf
- R_13.05 - Selmon_NoiseStudyReport_May2021.pdf
- R_13.06 – Selmon_PondSitingReport_20210617.pdf
- R_13.07 – Selmon_PreliminaryEngineeringReport_2021.pdf
- R_13.08 – Selmon_ProjectEnvironmentalImpactReport_June2021.pdf
- R_13.09 – Selmon_ProjectTrafficAnalysisReport_May2021.pdf
- R_13.10 – Selmon_VisionZero_ExecutiveSummary_April2020.pdf

R_14 - BIM_QC_Checklist - Civil.docx

R_15 - BIM_QC_Checklist - Structures.docx

R_16 - Project_Execution_Plan(PXP)_Template.docx

R_17– Bay to Bay Concept Final.pdf

R_18- Granada_Outfall_Drainage Technical Memo (12-13-2021).pdf

R_19 – So_Albany_Pond_PumpStation_Orig_PlanExcerpts.pdf

R_20 - Hills_River_Bridge_Exist_Aesthetic_Lighting_Info.pdf

R_21_So_Selmon_PD&E_Bridge_Reports.zip

R_22 -South_Selmon_Safety_RFP_Geotechnical_Data_Report.pdf

R_23 - Selmon PDE Preliminary Geotech Structures Report.pdf

R_24 - Selmon PDE Preliminary RoadwaySoilSurvey.pdf

R_25_CSX_Tampa S Selmon Xpwy_Fully exe PE Agr.pdf

R_26 - THEA-SS_Draft_PD&E_WQIE form_01082021.pdf

R_27 – THEA Contamination Notes

R_28 – Albany-Swann.zip

R_29 – Granada.zip

R_30 – AestheticLightingInfo_HillsRiverBridge.pdf

R_31 - Fiber Trak Map_HimesToFlorida_20230113.kmz

R_32 – TCC – Structures_Plans.pdf

R_33 - ITS_Managed Field Ethernet Switch_Specifications.pdf

R_34 – GENRAL INFO PKG FOR TRAF SIGNAL CONTRACTORS-Rev 6.28.16.pdf

R_35 – UAO RGSAPM As-builts.pdf

R_37 – COT Krause Generator.pdf

AMENDMENT

X.I.2.ww; DESIGN AND CONSTRUCTION CRITERIA, Structure Plans, Criteria; Page 93:

Correction: Revised Inside Shoulder Width

ww. The ultimate bridges from the west end of the bridges west of Bayshore Boulevard to the east end of the span just west of Franklin Street shall be designed, detailed and constructed per the RFP Documents (Reference Document R_13 Selmon_PreliminaryEngineeringReport_2021.pdf) and as shown below as part of this contract:

Typical Section Eastbound and Westbound

- i. Outside Traffic Railing: Index 521-427
- ii. Outside Shoulder: 5'-0"
- iii. Auxiliary Lane: 11'-0"
- iv. Travel Lane: 12'-0"
- v. Travel Lanes: 2 Lanes at 11'-0"
- vi. Travel Lane: 11'-0"
- vii. Inside Shoulder: 4'-0"
- viii. Median Traffic Railing: Index 521-426

AMENDMENT

Revise the attachments below and ATTACHMENTS; 5th Page at front of document:

Correction: Revised Incentive/Disincentive

ATTACHMENTS

The Attachments listed below are hereby incorporated into and made a part of this Request for Proposal (RFP) as though fully set forth herein.

A_001 - Division I Design-Build Specifications BWP 06-21-2022.docx

A_002 - Division I Special Provisions identified by the Authority for this Project:

A_002.01 - Public Records (SP0030900)

A_002.02 - Permits and Licenses (No free passes will be issued to the Contractor for use on the Toll Facility) (SP0070201)

A_002.03 - Preservation of Property for Toll Facilities (SP0071101-tolls)

- A_002.04 - Equal Employment Opportunity Requirements (SP0072700)
- A_002.05 - Preference to State Residents (SP0072800)
- A_002.06 - Contaminated Material – Mercury-Containing Devices and Lamps (SP0080409)
- A_002.07 - Prosecution and Progress - Damage Recovery (SP0081200)
- A_002.08 - Legal Requirements and Responsibility to the Public - E-Verify (SP0072900)
- A_002.09 - Legal Requirements and Responsibility to the Public - Scrutinized Companies (SP0073000)
- A-003 - FDOT Divisions II and III Special Provisions identified by the Authority for this Project:
 - A_003.01 - Mobilization (SP1010000DB)
 - A_003.02 - Contractor Quality Control General Requirements (SP1050813DB)
 - A_003.03 - Structures Foundations (SP4550000DB)
 - A_003.04 – Value Added Bridge Components (Dev475)
 - A_003.05 – sp0081300_Inc-Dis_SoSelmon_East_End_& EB_Noise_052722_Rev012723.pdf
 - A_003.06 – sp00813No_Excuse_Bonus_East_End_052722_Rev012723.pdf