



Bubble Callouts	Description	Utility Owner
1	Remove Existing Pedestal	BRIGHT HOUSE NETWORKS
2	Proposed BHN Pullbox To Be Installed	BRIGHT HOUSE NETWORKS
3	Remove Existing 24" x 36" Pullbox	BRIGHT HOUSE NETWORKS
4B	To Be Adjusted	CITY OF TAMPA WASTEWATER
4C	To Be Adjusted	CITY OF TAMPA WATER
4D	To Be Adjusted	BRIGHT HOUSE NETWORKS
4E	To Be Adjusted	FRONTIER COMMUNICATIONS
5A	To Be Removed	CITY OF TAMPA WATER
5C	To Be Removed	TECO
5D	To Be Removed	FRONTIER COMMUNICATIONS
6	Fire Hydrant To Be Installed	CITY OF TAMPA WATER
7	DIP Water Main To Be Installed	CITY OF TAMPA WATER
8	To Remain	TECO
8A	To Remain	FRONTIER COMMUNICATIONS
9	To Be Grouted	FRONTIER COMMUNICATIONS
10	Conduit To Be Installed	FRONTIER COMMUNICATIONS
11A	Pole To Be Installed	TECO
12	To Be Modified	TECO

CURVE DATA TWIGGS-1  
 PI STA. = 23+62.90  
 Δ = 21° 28' 23" (RT)  
 D = 14° 08' 02"  
 T = 76.87  
 L = 151.93  
 R = 405.38  
 PC STA. = 22+86.04  
 PT STA. = 24+37.96

REVISIONS				MEGAN M. TETRO, P.E. FLORIDA PE NO. 76120 WANTMAN GROUP, INC. 3111 W. MARTIN LUTHER KING JR. BLVD., SUITE 375, TAMPA, FL 33607 CERTIFICATE OF AUTHORIZATION NO. 6091	TAMPA HILLSBOROUGH EXPRESSWAY AUTHORITY			SHEET NO.  5
DATE	DESCRIPTION	DATE	DESCRIPTION		ROAD	COUNTY	CONTRACT NO.	
					TWIGGS	HILLSBOROUGH	000419	